

**ADDENDUM NO. 2**  
**TO**  
CONTRACT DOCUMENTS  
**FOR**  
THE CITY OF MARQUETTE  
PRESQUE ISLE MARINA REHABILITATION PROJECT – PIER REPLACEMENT  
  
MAY 20, 2019

**Contractor shall list all addenda by number on the bid form to ensure conformity in the bid.**

Drawings, Specifications and/or Proposals are herein amended, expanded and/or modified, as hereinafter described, and become a part of the Contract Documents with the same force and effect as if incorporated, therein, originally. Any contrary provisions contained, or referred to, in Drawings and/or Specifications, shall remain applicable unless overridden by this Addendum. Revised or contrary provisions herein shall not affect any other part of the Contract Documents and any deletions, additions, substitutions and/or revisions mentioned, shall include all labor, materials, methods, modifications, etc. required for complete performance of the work.

This Addendum No. 2 consists of 2 pages.

**CLARIFICATIONS**

The following are clarifications to the project:

- If the north pier is not selected for removal, dredging near the north pier will not be required.
- If the dredging option is not selected, the bin-type fixed piers will be required to be excavated to elevation 593’.
- The sanitary sewer manhole will not be required to be replaced.
- Assume that there will be no material testing and there will be no special requirements for upland disposal.
- The Contractor will have the ability to restrict access to the site by closing the parking lot to traffic.

## CONTRACT DOCUMENT CHANGES

### ADVERTISEMENT FOR BIDS

Revise the bid receipt statement to read:

Bids must be received by 3:00 p.m. (local time) on **Friday, May 31, 2019** at the City of Marquette, Community Services, 401 Fair Avenue, Marquette, MI 49855. **Bids will be publicly opened at City Hall and read out loud after receipt.**

### SPECIAL PROVISIONS

Revise Special Provision No. 29 to read:

29. The Marina parking lot may be used as a staging area for non-aggregate/non-granular materials (concrete, metal, piping, wire, etc.) from the excavation of the bin-type fixed piers prior to disposal. **The Marina parking lot may also be used to stockpile excavated sediment and materials for hauling off-site.**

Add the following Special Provision:

30. Contractor pre- and post-bathymetric surveys will be required to be completed on a 25-foot grid with 5-foot shot intervals.

### PLAN SHEETS

Plan Sheet D4: Change gangway length dimension from 60' to 50'.

Contract documents will not be reissued to reflect these changes. These changes are referenced by this addendum.